Route 36 Speed and Reliability Corridor

2022 PSRC Regional FHWA Grant Program

Presenter: Matthew Crane

Total PSRC Regional FHWA Request: \$3.0M (STP)


Corridors Connecting Centers



ROUTE 36 CORRIDOR OVERVIEW

- Trolley bus route providing frequent, all-day service between Downtown Seattle and Othello via the Beacon Hill neighborhood
- 85,000 people and 255,000 jobs within ½ mile of the corridor today
- 2040 growth forecasts 65,000 new residents (+70%) and 31,000 new jobs (+12%)
- Supports multiple centers
 - Regional Growth Centers: Seattle Downtown and First Hill/Capitol Hill
 - Local Centers: North Beacon Hill and Othello Residential Urban Villages
 - Metro local transit centers: Beacon Hill and Othello Link Light Rail Stations





ROUTE 36 RIDERSHIP

- Serves diverse communities in South Seattle that rely on transit to travel
 - 60% in minority demographic
 - 20% households in poverty
 - 14% living with a disability
 - 37% without access to a vehicle
- One of Metro's highest ridership routes through COVID-19 pandemic
 - Fall 2019: 9,200 weekday boardings (#6)
 - Fall 2021: 5,400 weekday boardings (#6)
 - Accounts for 2% of all Metro's ridership








ROUTE 36 CORRIDOR CONGESTION

- Increased traffic congestion causes slow, unreliable transit experience (Fall 2019)
 - o 40% of afternoon peak period trips are late
 - Average bus speed is 12 mph during afternoon peak
 - 72% on-time performance
- Project goals
 - Improve peak period travel times by up 10% (5 min faster)
 - o Improve on-time performance to meet target 80%
 - Resulting increased ridership





POTENTIAL IMPROVEMENTS

- Metro has developed draft list of improvements targeting congested areas along the corridor
- Additional study in 2022-2023 will perform technical analysis and outreach to develop additional improvements and prioritization
- Coordination with City of Seattle for compatibility with Beacon Hill Bike Project





Potential Improvement	Location
Next-Gen Transit Signal Priority	Up to 30 signalized intersections along project corridor
BAT Lane (NB direction only); transit queue jumps + signal phasing improvements	Beacon Ave S / 15th Ave S
Bus zone bulb-outs and/or stop rebalancing	12th Ave S and 14th Ave S at: Golf Dr S, S Judkins St, S Atlantic St, S Massachusetts St
BAT Lanes (both directions); phasing improvements + queue jumps	Beacon Ave S / S Columbian Way
SB bus zone bulb-out	Beacon Ave S / S Bayview St
SB BAT lane	Beacon Ave S (14th Ave S - S Lander St)
BAT Lanes (both directions); transit queue jumps + signal phasing improvements	Beacon Ave S / S Spokane St
Bus zone bulb-outs and/or stop rebalancing	Beacon Ave S at: S Stevens St, S Hanford St
NB bus zone bulb-out	Beacon Ave S / S Spokane St
BAT lane (NB only); transit queue jumps + signal phasing improvements	Beacon Ave S / S Graham St
NB transit queue jump	Beacon Ave S / S Lander St
Bus zone bulb-outs and/or stop rebalancing	Beacon Ave S at: S Dawson St, S Brandon St, S Orcas St, S Spencer St
In-lane stops	Beacon Ave S, S Myrtle St, and S Myrtle Pl at: S Holly St, 27th Ave S, 32nd Ave S, S Holly Park Dr
Signal phasing improvements	Beacon Ave S / S Myrtle St



ANTICIPATED BENEFITS




Faster & more reliable transit trips
Access to more jobs and opportunities
Higher person-capacity on corridor





Save 12,000 kg CO per year 8,000 gallons of fuel per year



Improve connections to regional transportation network

- Improves intermodal connections to Sound Transit Link light rail,
 Sounder Rail, Seattle Streetcar, downtown ferry/water taxi, bikeways and regional trails
- Improves mobility to Downtown Seattle Regional Growth Centers,
 Seattle urban villages, and Metro transit activity centers



FUNDING GOAL

Project Phase	Amount	Funding Source
PE & Design (2024-2026)	\$1,176,000	Local
Construction	\$1,188,145	Local match
(2026)	\$3,000,000	STP Funds

Requesting \$3.0M from PSRC FHWA grant funding (Surface Transportation Program) for construction of speed and reliability improvements in 2026.

TOTAL \$5,364,590

Project schedule

PLANNING 2022-2023

PRELIMINARY DESIGN 2024-2025 FINAL DESIGN

CONSTRUCTION 2026

OPERATIONALLY COMPLETE
2026

\$3.0M requested from PSRC FHWA grant





Questions?



Matthew Crane
Route 36 Project Manager
mcrane@kingcounty.gov
(206) 263-9134

